

Date December 8. 1896

Estimate

Messrs Taylor & Co.  
Loughborough -

(Original Estimate)

# JOHN TAYLOR & CO



Successors to the  
ancient  
Firms of

WATTS, EAYRE & ARNOLD  
OF  
LEICESTER & ST NEOTS.

## BELL FOUNDERS.

### LOUGHBOROUGH.

## ESTIMATE

1896

Lsd

An estimate for new fittings for the  
peal of six bells belonging to Badesy Church -  
consisting of oak wheels, Elm headstocks,  
steel gudgeons fitted in bound iron bedplates,  
best hard gunmetal bearings in iron  
pedestals, ropes with flax ends and worsted  
salleys, rollers, stays, sliders, wrought  
iron clappers & strike the bells on fresh  
places and all necessary smithwork -  
the whole fitted up complete ready for fixing -

60. 0. 0

Very strong and massive cast  
iron H shaped framework of improved  
construction <sup>for 8 bells</sup> similar to that at top of  
page 29 of catalogue, well braced and  
firmly bolted together, standing upon  
and bolted to heavy rolled steel girders,  
with all requisite stays, plates, bolts,  
nuts and rivets - fitted up complete  
ready for fixing

Carried forward

100. 0. 0  
160. 0. 0

Brought forward

£ s d  
160 - 0 - 0

Taking down the old bells and framework,  
and fixing the whole of the above complete  
in the tower including all men's time and  
expenses with the exception of mason's work,  
leaving the bells in first class ringing order.

25 - 0 - 0

Carriage of all materials and tools  
to and from our works and the Church -  
altogether about 7 tons

8 - 15 - 0

£ 193 - 15 - 0

Estimate No. 2.

£ s d

For two smaller bells to complete the  
octave - to weigh together about 10 cwt  
and to be charged for at the rate of £5. 5.  
per cwt - Warranted cast of pure  
copper and tin

52 - 10 - 0

Fittings for bells as specified above

18 - 0 - 0

Carriage and fixing

4 - 10 - 0

£ 75 - 0 - 0

If the six bells are sent to the foundry to be turned and fitted with iron headstocks there will be no extra charge except for the carriage to and from which will be about 35/- per ton each way -

The above estimates do not include any work to the clock, Carillon machine or their hammers, nor to the floors and masonry of the tower -

All materials and workmanship to be of the best quality and the whole to be completed in a substantial and satisfactory manner -

Terms - 2 1/2% discount for cash within one month of completion -

December 8<sup>th</sup> 1896.

John Taylor & Co